MYSORE DIVISION.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 5th March 1905, for constructing lines for Palace Barr Band and Body Guard at Mysore. The estimate is divided into four groups. The whole or any of the groups may be tendered. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1907.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore between the hours of 12 noon and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 2,500 for the whole or Rs. 1,000 for groups II and Rs. 500 for each of groups Nos. 1, 3 and 4, in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for constructing lines for Palace Barr Band and Body Guard at Mysore, whole or group Nos."; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, P. W. Secretary, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Group No. 1.

Sub-heads.	Details of work.	Per	Quantity.
(*a*) Barr Commandants.	Earthwork excavation	C. yd.	2,363
(*b*) Body Guard Commandant	Filling foundations in concrete	C. ft.	4,376
(*c*) Commissioned Officers.	Rough stone in chunam	,,	51,064
(*d*) Body Guard line.	Burnt stone in chunam	,,	9,832
(*e*) Stables.	Burnt brick in chunam	,,	41,144
	Burnt brick in mud	,,	89,923
	Burnt stone slabs	S. ft.	10,196
	Segmental arch work	C. ft.	26
	Cut stone work	No.	26
	Plastering with chunam	Sqr.	898·61
	Whitewashing	,,	904·05
	Color-washing	,,	687·52
	Teakwood work	C. ft.	1184·99
	Roofing with 1st class Mangalore tiles ..	Sqr.	509·88
	Mangalore tiles flooring	,,	16·52
	Burnt stone flagging over 3" concrete ..	,,	33·16
	Ridge-tiles set in mortar	R. ft.	1,430
	Ventilating tiles	No.	344
	Ornamental eave boards	R. ft.	1,226
	Teakwood ceiling	Sqr.	11·52
	Teakwood doors, pannelled	S. ft.	698
	Do battened	,,	5,285
	Windows pannelled outside glazed ...	,,	192
	Ventilators, glazed...	,,	216
	Zinc gutters, walls ...	R. ft.	208

Group No. 1.—conld.

Sub-heads.	Details of work.	Per	Quantity.
	Coping brick in chunam	R. ft.	4,331
	Ornamental finials	No.	14
	Tarring	Sqr.	75·00
	Honne wood work	C. ft.	1402·46
	Mud plastering	Sqr.	1003·57
	Ordinary eave boards	R. ft.	158
	Flooring with gravel	C. yd.	735
	Cutting groves in the pillars	No.	52
	Burnt stone slabs posts	,,	84
	Cross bamboos for stalls	,,	108
	Earth filling basement	L. S.	
	Forming nitches and wall pegs, etc. ...	,,	

Group No. II.

Sub-heads.	Details of work.	Per	Quantity.
8 Lines of Barr Sepoys. 1 Line of 36 huts. 1 Line for camp followers.	Earthwork	C. yd.	4,647
	Rough stone in chunam	C. ft.	2,11,920
	Burnt brick in chunam	,,	98,236
	Burnt brick in mud	,,	3,72,884
	Burnt stone slabs dressed and put up ..	S. ft.	35,069
	Honne wood doors and windows ...	,,	24,436
	Tarring privy	L. S.	
	Chacolate painting	Sqr.	650·35
	Wood work, honne	C. ft.	6224·49
	Ordinary eave boards	R. ft.	763
	Finials	No.	20
	Roofing with 1st class Mangalore tiles ..	Sqr.	1345·75
	Ridge tiles	R. ft.	3,527
	Ventilating tiles	No.	964
	Plastering with chunam	Sqr.	3557·12
	Mud plastering	,,	3960·24
	Painting with chunam	,,	155·52
	Flooring with gravel	C. yd.	3,485
	Whitewashing	Sqr.	3960·24
	Color-washing	,,	3557·12
	Filling basement and forming nitches wall pegs.	L. S.	

Group No. III.

Sub-heads.	Details of work.	Per	Quantity.
Opening out roads and constructing drains, latrines and Barr Barraks.	Cutting and forming roads	C. yd.	6,557
	Gravel excavating and forming ...	,,	783
	Concrete	C. ft.	10,856
	Slabs stone 3″ dressed and fitted up	S. ft.	

Group No. III.—contd.

Sub-heads.	Details of work.	Per	Quantity.
	Burnt brick in chunam	C. ft.	13,114
	Flooring with rough stone	C. yd.	4
	Plastering with chunam	Sqr.	157·22
	Guard stones	No.	8
	Four tunnels of 14 feet in length ...	L. S.	
	Filling foundation rough stone in chunam ...	C. ft.	1,431
	Burnt brick in mud	„	2,544
	Stone slabs flooring over 3″ concrete ...	Sqr.	45·69
	Honne wood work	C. ft.	60·60
	Honey-comb work	Sqr.	3·15
	Zinc sheets roofing and for seats ...	S. ft.	3,216
	Brick in chunam coping	R. ft.	96
	Burnt brick circular pillars	C. ft.	92
	Teakwood work	„	250·94
	Cornice work around top and base of pillars.	L. S.	
	Roofing with Mangalore tiles	Sqr.	46·47
	Teakwood doors, pannelled	S. ft.	216
	Do windows with iron bars ..	„	122
	Do ventilating glazed	„	20
	Ornamental eave boards	R. ft.	436
	Whitewashing	S. ft.	68·19
	Color-washing	„	22·89
	Teakwood stands for placing rifles ..	L. S.	
	Chacolate painting	Sqr.	1,209
	Wood oiling	L. S.	
	Clearing site	„	
	Filling basement	„	
	Drawing wells each 6′ feet in diameter ..	„	

Group No. IV.

Sub-heads.	Details of work.	Per	Quantity.
Two lines of 52 huts for Bandsmen. 1 latrine and 1 Dobbee kohava.	Earthwork excavation	C. yd.	1,735
	Rough stone in chunam	C. ft.	26,719
	Brick in chunam	„	21,372
	Brick in mud	„	83,266
	Burnt stone slabs, dressed	S. ft.	7,826
	Honne wood doors and windows ...	„	15,376
	Brick in chunam coping	R. ft.	4,794
	Tarring	L. S.	
	Chacolate painting	Sqr.	143·12
	Wood work, honne	C. ft.	1394·40
	Eave boards, ordinary	R. ft.	158
	Finials	No.	4
	Roofing with Mangalore tiles	Sqr.	296·40
	Ridge tiles	R. ft	760
	Ventilating tiles	No.	208
	Plastering with chunam	Sqr.	803·52
	Mud plastering	„	880·62
	Painting with chunam	„	35·67
	Color-washing	Sqr.	782·14
	Flooring with gravel	C. yd.	762
	Whitewashing	„	880·62
	Filling basement	L. S.	
	Stone slabs flooring over 3″ concrete ...	Sqr.	6·85
	Honey-comb work	„	1·05
	Zinc sheets roofing	„	10·72
	Clearing site	L. S.	
	U-shape drain	„	
	Concrete work	C. ft.	81

V. ARUNACHALA MUDALIAR, *Executive Engineer.*